


STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒

APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Monument Butte East State R-36-8-16	
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT MONUMENT BUTTE	
4. TYPE OF WELL Oil Well <input type="checkbox"/> Coalbed Methane Well: NO <input type="checkbox"/>						5. UNIT or COMMUNITIZATION AGREEMENT NAME GMBU (GRRV)	
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY						7. OPERATOR PHONE 435 646-4825	
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052						9. OPERATOR E-MAIL mcrozier@newfield.com	
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) ML-22061			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>	
13. NAME OF SURFACE OWNER (if box 12 = 'fee')						14. SURFACE OWNER PHONE (if box 12 = 'fee')	
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')	
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>	
20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN	
LOCATION AT SURFACE	842 FSL 2124 FEL	SWSE	36	8.0 S	16.0 E	S	
Top of Uppermost Producing Zone	1317 FSL 2612 FWL	SESW	36	8.0 S	16.0 E	S	
At Total Depth	1317 FSL 2612 FWL	SESW	36	8.0 S	16.0 E	S	
21. COUNTY DUCHESNE		22. DISTANCE TO NEAREST LEASE LINE (Feet) 1317		23. NUMBER OF ACRES IN DRILLING UNIT 20			
		25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 1408		26. PROPOSED DEPTH MD: 6308 TVD: 6308			
27. ELEVATION - GROUND LEVEL 5355		28. BOND NUMBER B001834		29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 43-7478			
ATTACHMENTS							
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES							
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER				<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN			
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)				<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER			
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)				<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP			
NAME Mandie Crozier		TITLE Regulatory Tech		PHONE 435 646-4825			
SIGNATURE		DATE 08/17/2009		EMAIL mcrozier@newfield.com			
API NUMBER ASSIGNED 43013501140000		APPROVAL <div style="text-align: center;">  Permit Manager </div>					


Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Prod	7.875	5.5	0	6308		
Pipe	Grade	Length	Weight			
	Grade J-55 LT&C	6308	15.5			

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	12.25	8.625	0	400		
Pipe	Grade	Length	Weight			
	Grade J-55 ST&C	400	24.0			


T8S, R16E, S.L.B.&M.

NEWFIELD PRODUCTION COMPANY

WELL LOCATION, MONUMENT BUTTE EAST R-36-8-16, LOCATED AS SHOWN IN THE SW 1/4 SE 1/4 OF SECTION 36, T8S, R16E, S.L.B.&M. DUCHESNE COUNTY, UTAH.




THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE SURVEYED: 6-19-09	SURVEYED BY: T.H.
DATE DRAWN: 6-25-09	DRAWN BY: M.W.
REVISED:	SCALE: 1" = 1000'



◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are base on LOCATION: an N.G.S. OPUS Correction. LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'

MONUMENT BUTTE EAST R-36-8-16
(Surface Location) NAD 83
LATITUDE = 40° 04' 09.95"
LONGITUDE = 110° 03' 57.34"





Project: USGS Myton SW (UT)
Site: SECTION 36
Well: R-36-8-16
Wellbore: Wellbore #1
Design: Design #1



Azimuths to True North
Magnetic North: 11.55°

Magnetic Field
Strength: 52503.4snT
Dip Angle: 65.87°
Date: 2009/07/16
Model: IGRF200510

KOP @ 600'
DOGLENG RATE 1.5 DEG/100
TARGET RADIUS IS 75'



WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
R-36-8-16 TGT	6260.0	468.0	-557.0	Circle (Radius: 75.0)

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1111.2	7.67	310.04	1109.6	22.0	-26.1	1.50	310.04	34.2	
4	6308.0	7.67	310.04	6260.0	468.0	-557.0	0.00	0.00	727.5	R-36-8-16 TGT





NEWFIELD EXPLORATION

USGS Myton SW (UT)

SECTION 36

R-36-8-16

Wellbore #1

Plan: Design #1

Standard Planning Report

16 July, 2009





HATHAWAY BURNHAM

Planning Report



Database: EDM 2003.21 Single User Db
Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 36
Well: R-36-8-16
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well R-36-8-16
TVD Reference: R-36-8-16 @ 5367.0ft
MD Reference: R-36-8-16 @ 5367.0ft
North Reference: True
Survey Calculation Method: Minimum Curvature

Project USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA

Map System: US State Plane 1983
Geo Datum: North American Datum 1983
Map Zone: Utah Central Zone

System Datum: Mean Sea Level
 Using geodetic scale factor

Site SECTION 36, SEC 26 T8S, R16E

Site Position: Northing: 7,202,697.00 ft Latitude: 40° 5' 3.401 N
From: Lat/Long Easting: 2,045,250.00 ft Longitude: 110° 3' 10.915 W
Position Uncertainty: 0.0 ft Slot Radius: " Grid Convergence: 0.93 °

Well R-36-8-16, SHL LAT: 40 04 09.95, LONG: -110 03 57.34

Well Position +N/-S -5,409.1 ft Northing: 7,197,231.22 ft Latitude: 40° 4' 9.950 N
 +E/-W -3,608.5 ft Easting: 2,041,728.99 ft Longitude: 110° 3' 57.340 W
Position Uncertainty 0.0 ft Wellhead Elevation: ft Ground Level: 5,337.0 ft

Wellbore Wellbore #1

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	2009/07/16	11.55	65.87	52,503

Design Design #1

Audit Notes:

Version: Phase: PROTOTYPE Tie On Depth: 0.0

Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	6,260.0	0.0	0.0	310.04

Plan Sections

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,111.2	7.67	310.04	1,109.6	22.0	-26.1	1.50	1.50	0.00	310.04	
6,308.0	7.67	310.04	6,260.0	468.0	-557.0	0.00	0.00	0.00	0.00	R-36-8-16 TGT

NEWFIELD



HATHAWAY BURNHAM

Planning Report



Database: EDM 2003.21 Single User Db
 Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 36
 Well: R-36-8-16
 Wellbore: Wellbore #1
 Design: Design #1

Local Co-ordinate Reference:
 TVD Reference:
 MD Reference:
 North Reference:
 Survey Calculation Method:

Well R-36-8-16
 R-36-8-16 @ 5367.0ft
 R-36-8-16 @ 5367.0ft
 True
 Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	1.50	310.04	700.0	0.8	-1.0	1.3	1.50	1.50	0.00
800.0	3.00	310.04	799.9	3.4	-4.0	5.2	1.50	1.50	0.00
900.0	4.50	310.04	899.7	7.6	-9.0	11.8	1.50	1.50	0.00
1,000.0	6.00	310.04	999.3	13.5	-16.0	20.9	1.50	1.50	0.00
1,100.0	7.50	310.04	1,098.6	21.0	-25.0	32.7	1.50	1.50	0.00
1,111.2	7.67	310.04	1,109.6	22.0	-26.1	34.2	1.50	1.50	0.00
1,200.0	7.67	310.04	1,197.7	29.6	-35.2	46.0	0.00	0.00	0.00
1,300.0	7.67	310.04	1,296.8	38.2	-45.4	59.3	0.00	0.00	0.00
1,400.0	7.67	310.04	1,395.9	46.8	-55.7	72.7	0.00	0.00	0.00
1,500.0	7.67	310.04	1,495.0	55.3	-65.9	86.0	0.00	0.00	0.00
1,600.0	7.67	310.04	1,594.1	63.9	-76.1	99.4	0.00	0.00	0.00
1,700.0	7.67	310.04	1,693.2	72.5	-86.3	112.7	0.00	0.00	0.00
1,800.0	7.67	310.04	1,792.3	81.1	-96.5	126.1	0.00	0.00	0.00
1,900.0	7.67	310.04	1,891.4	89.7	-106.7	139.4	0.00	0.00	0.00
2,000.0	7.67	310.04	1,990.5	98.3	-116.9	152.7	0.00	0.00	0.00
2,100.0	7.67	310.04	2,089.6	106.8	-127.2	166.1	0.00	0.00	0.00
2,200.0	7.67	310.04	2,188.7	115.4	-137.4	179.4	0.00	0.00	0.00
2,300.0	7.67	310.04	2,287.8	124.0	-147.6	192.8	0.00	0.00	0.00
2,400.0	7.67	310.04	2,387.0	132.6	-157.8	206.1	0.00	0.00	0.00
2,500.0	7.67	310.04	2,486.1	141.2	-168.0	219.5	0.00	0.00	0.00
2,600.0	7.67	310.04	2,585.2	149.8	-178.2	232.8	0.00	0.00	0.00
2,700.0	7.67	310.04	2,684.3	158.3	-188.4	246.1	0.00	0.00	0.00
2,800.0	7.67	310.04	2,783.4	166.9	-198.7	259.5	0.00	0.00	0.00
2,900.0	7.67	310.04	2,882.5	175.5	-208.9	272.8	0.00	0.00	0.00
3,000.0	7.67	310.04	2,981.6	184.1	-219.1	286.2	0.00	0.00	0.00
3,100.0	7.67	310.04	3,080.7	192.7	-229.3	299.5	0.00	0.00	0.00
3,200.0	7.67	310.04	3,179.8	201.3	-239.5	312.9	0.00	0.00	0.00
3,300.0	7.67	310.04	3,278.9	209.8	-249.7	326.2	0.00	0.00	0.00
3,400.0	7.67	310.04	3,378.0	218.4	-259.9	339.5	0.00	0.00	0.00
3,500.0	7.67	310.04	3,477.1	227.0	-270.2	352.9	0.00	0.00	0.00
3,600.0	7.67	310.04	3,576.2	235.6	-280.4	366.2	0.00	0.00	0.00
3,700.0	7.67	310.04	3,675.3	244.2	-290.6	379.6	0.00	0.00	0.00
3,800.0	7.67	310.04	3,774.4	252.8	-300.8	392.9	0.00	0.00	0.00
3,900.0	7.67	310.04	3,873.5	261.4	-311.0	406.2	0.00	0.00	0.00
4,000.0	7.67	310.04	3,972.6	269.9	-321.2	419.6	0.00	0.00	0.00
4,100.0	7.67	310.04	4,071.8	278.5	-331.5	432.9	0.00	0.00	0.00
4,200.0	7.67	310.04	4,170.9	287.1	-341.7	446.3	0.00	0.00	0.00
4,300.0	7.67	310.04	4,270.0	295.7	-351.9	459.6	0.00	0.00	0.00
4,400.0	7.67	310.04	4,369.1	304.3	-362.1	473.0	0.00	0.00	0.00
4,500.0	7.67	310.04	4,468.2	312.9	-372.3	486.3	0.00	0.00	0.00
4,600.0	7.67	310.04	4,567.3	321.4	-382.5	499.6	0.00	0.00	0.00
4,700.0	7.67	310.04	4,666.4	330.0	-392.7	513.0	0.00	0.00	0.00
4,800.0	7.67	310.04	4,765.5	338.6	-403.0	526.3	0.00	0.00	0.00
4,900.0	7.67	310.04	4,864.6	347.2	-413.2	539.7	0.00	0.00	0.00
5,000.0	7.67	310.04	4,963.7	355.8	-423.4	553.0	0.00	0.00	0.00
5,100.0	7.67	310.04	5,062.8	364.4	-433.6	566.4	0.00	0.00	0.00
5,200.0	7.67	310.04	5,161.9	372.9	-443.8	579.7	0.00	0.00	0.00



HATHAWAY BURNHAM

Planning Report



Database: EDM 2003.21 Single User Db
Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 36
Well: R-36-8-16
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well R-36-8-16
TVD Reference: R-36-8-16 @ 5367.0ft
MD Reference: R-36-8-16 @ 5367.0ft
North Reference: True
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,300.0	7.67	310.04	5,261.0	381.5	-454.0	593.0	0.00	0.00	0.00
5,400.0	7.67	310.04	5,360.1	390.1	-464.2	606.4	0.00	0.00	0.00
5,500.0	7.67	310.04	5,459.2	398.7	-474.5	619.7	0.00	0.00	0.00
5,600.0	7.67	310.04	5,558.3	407.3	-484.7	633.1	0.00	0.00	0.00
5,700.0	7.67	310.04	5,657.4	415.9	-494.9	646.4	0.00	0.00	0.00
5,800.0	7.67	310.04	5,756.6	424.4	-505.1	659.8	0.00	0.00	0.00
5,900.0	7.67	310.04	5,855.7	433.0	-515.3	673.1	0.00	0.00	0.00
6,000.0	7.67	310.04	5,954.8	441.6	-525.5	686.4	0.00	0.00	0.00
6,100.0	7.67	310.04	6,053.9	450.2	-535.7	699.8	0.00	0.00	0.00
6,200.0	7.67	310.04	6,153.0	458.8	-546.0	713.1	0.00	0.00	0.00
6,308.0	7.67	310.04	6,260.0	468.0	-557.0	727.5	0.00	0.00	0.00

Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
R-36-8-16 TGT - plan hits target - Circle (radius 75.0)	0.00	0.00	6,260.0	468.0	-557.0	7,197,690.23	2,041,164.62	40° 4' 14.575 N	110° 4' 4.505 W

NEWFIELD PRODUCTION COMPANY
MONUMENT BUTTE EAST STATE R-36-8-16
AT SURFACE: SW/SE SECTION 36, T8S, R16E
DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta	0 – 1570'
Green River	1570'
Wasatch	6308'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation 1570' – 6308' – Oil

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sampled Interval	Date Sampled
Flow Rate	Temperature
Hardness	pH
Water Classification (State of Utah)	Dissolved Calcium (Ca) (mg/l)
Dissolved Iron (Fe) (ug/l)	Dissolved Sodium (Na) (mg/l)
Dissolved Magnesium (Mg) (mg/l)	Dissolved Carbonate (CO ₃) (mg/l)
Dissolved Bicarbonate (NaHCO ₃) (mg/l)	Dissolved Chloride (Cl) (mg/l)
Dissolved Sulfate (SO ₄) (mg/l)	Dissolved Total Solids (TDS) (mg/l)

4. **PROPOSED CASING PROGRAM:**

a. Casing Design: Monument Butte East State R-36-8-16

Size	Interval		Weight	Grade	Coupling	Design Factors		
	Top	Bottom				Burst	Collapse	Tension
Surface casing 8-5/8"	0'	400'	24.0	J-55	STC	2,950 13.15	1,370 10.77	244,000 25.42
Prod casing 5-1/2"	0'	6,308'	15.5	J-55	LTC	4,810 2.40	4,040 2.01	217,000 2.22

Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient – gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure – gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
Pore pressure at surface casing shoe = 8.33 ppg
Pore pressure at prod casing shoe = 8.33 ppg
Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. Cementing Design: Monument Butte East State R-36-8-16

Job	Fill	Description	Sacks	OH Excess*	Weight (ppg)	Yield (ft ³ /sk)
			ft ³			
Surface casing	400'	Class G w/ 2% CaCl	183 215	30%	15.8	1.17
Prod casing Lead	4,308'	Prem Lite II w/ 10% gel + 3% KCl	298 970	30%	11.0	3.26
Prod casing Tail	2,000'	50/50 Poz w/ 2% gel + 3% KCl	363 451	30%	14.3	1.24

*Actual volume pumped will be 15% over the caliper log

- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
- Compressive strength of tail cement: 2500 psi @ 24 hours.

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well.

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

From surface to ± 350 feet will be drilled with an air/mist system. From about 350 feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite.

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 400' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.

10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

Ten Point Well Program &
Thirteen Point Well Program
Page 4 of 9

It is anticipated that the drilling operations will commence the fourth quarter of 2009, and take approximately seven (7) days from spud to rig release.





EXHIBIT C




DATE: 07-02-2009

Existing Road

"A"





NEWFIELD
Exploration Company

Monument Butte East R-36-8-16 (Proposed Well)
Monument Butte East 15-36-8-16 (Existing Well)
 Pad Location: SWSE SEC. 36, T8S, R16E, S.L.B.&M.






Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078


SCALE: 1" = 2,000'
DRAWN BY: mw
DATE: 07-02-2009

Legend

 Existing Road

TOPOGRAPHIC MAP

"B"



Monument Butte East R-36 (Proposed Well)
Monument Butte East 15-36 (Existing Well)

Existing Waterline

Existing Gas Pipeline



NEWFIELD
Exploration Company

Monument Butte East R-36-8-16 (Proposed Well)
Monument Butte East 15-36-8-16 (Existing Well)
Pad Location: SWSE SEC. 36, T8S, R16E, S.L.B.&M.



Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078


SCALE: 1" = 2,000'
DRAWN BY: mw
DATE: 07-02-2009


Legend

Roads

TOPOGRAPHIC MAP

"C"





NEWFIELD
Exploration Company

Monument Butte East R-36-8-16 (Proposed Well)
Monument Butte East 15-36-8-16 (Existing Well)
Pad Location: SWSE SEC. 36, T8S, R16E, S.L.B.&M.

Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: mw
DATE: 07-02-2009

Legend

- Pad Location
- Bottom Hole Location
- One-Mile Radius

Exhibit "B"

NEWFIELD PRODUCTION COMPANY
MONUMENT BUTTE EAST STATE R-36-8-16
AT SURFACE: SW/SE SECTION 36, T8S, R16E
DUCHESNE COUNTY, UTAH

THIRTEEN POINT SURFACE PROGRAM

1. EXISTING ROADS

See attached **Topographic Map "A"**

To reach Newfield Production Company well location site Monument Butte East State R-36-8-16 located in the SW ¼ SE ¼ Section 36, T8S, R16E, S.L.B. & M., Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.4 miles \pm to the junction of this highway and UT State Hwy 53; proceed southeasterly along Hwy 53 - 6.2 miles \pm to it's junction with an existing road to the southwest; proceed southwesterly - 2.8 miles \pm to it's junction with an existing road to the southeast; proceed southeasterly - 1.3 miles \pm to it's junction with an existing road to the east; proceed northeasterly - 1.4 miles \pm to the existing 15-36-8-16 well location.

The highways mentioned in the foregoing paragraph are bituminous surfaced roads to the point where Highway 216 exists to the South, thereafter the roads are constructed with existing materials and gravel. The highways are maintained by Utah State road crews. All other roads are maintained by County crews.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal.

2. PLANNED ACCESS ROAD

There is no proposed access road for this location. The proposed well will be drilled off of the existing 15-36-8-16 well pad. See attached **Topographic Map "B"**.

There will be no new gates or cattle guards required.

3. LOCATION OF EXISTING WELLS

Refer to **EXHIBIT B**.

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

The proposed well will be drilled directionally off of the existing 15-36-8-16 well pad. There will be a pumping unit and a short flow line added to the existing tank battery for the proposed R-36-8-16.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted Carlsbad Canyon. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck for drilling purposes from the following water sources:

Johnson Water District
Water Right: 43-7478

Neil Moon Pond
Water Right: 43-11787

Maurice Harvey Pond
Water Right: 47-1358

Newfield Collector Well
Water Right: 41-3530 (A30414DV, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

The proposed Monument Butte East State R-36-8-16 will be drilled off of the existing 15-36-8-16 well pad. No additional surface disturbance will be required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

Immediately upon first production, all produced water will be confined to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the

produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project.

Water not meeting quality criteria, is disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

8. **ANCILLARY FACILITIES:**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT:**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. **PLANS FOR RESTORATION OF SURFACE:**

a) **Producing Location**

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

b) **Dry Hole Abandoned Location**

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP:** State of Utah

12. **OTHER ADDITIONAL INFORMATION:**

- a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.
- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the Monument Butte East State R-36-8-16, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the Monument Butte East State R-36-8-16 Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office shall be notified upon site completion prior to moving on the drilling rig.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**

Representative

Ten Point Well Program &
Thirteen Point Well Program
Page 8 of 8


Name: Tim Eaton
Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052
Telephone: (435) 646-3721

Certification

Please be advised that Newfield Production Company is considered to be the operator of well #R-36-8-16, SW/SE Section 36, T8S, R16E, LEASE #ML-22061, Duchesne County, Utah and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Bond #B001834.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

8/17/09
Date


Mandie Crozier
Regulatory Specialist
Newfield Production Company

NEWFIELD PRODUCTION COMPANY

WELL PAD INTERFERENCE PLAT

MONUMENT BUTTE EAST R-36-8-16 (Proposed Well)


MONUMENT BUTTE EAST 15-36-8-16 (Existing Well)

Pad Location: SWSE Section 36, T8S, R16E, S.L.B.&M.



TOP HOLE FOOTAGES

R-36-8-16 (PROPOSED)
842' FNL & 2124' FEL



Note:

Bearings are based on
GLO Information.

RELATIVE COORDINATES From top hole to bottom hole

WELL	NORTH	EAST
R-36-8-16	468'	-557'

LATITUDE & LONGITUDE Surface position of Wells (NAD 83)

WELL	LATITUDE	LONGITUDE
15-36-8-16	40° 04' 09.74"	110° 03' 57.40"
R-36-8-16	40° 04' 09.95"	110° 03' 57.34"

Note:

Bearings are based
on GLO Information.

BOTTOM HOLE FOOTAGES

R-36-8-16 (PROPOSED)
1317' FSL & 2673' FEL

SURVEYED BY: T.H.	DATE SURVEYED: 06-19-09
DRAWN BY: M.W.	DATE DRAWN: 06-25-09
SCALE: 1" = 50'	REVISED:


Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

NEWFIELD PRODUCTION COMPANY

MONUMENT BUTTE EAST R-36-8-16 (Proposed Well)

MONUMENT BUTTE EAST 15-36-8-16 (Existing Well)

Pad Location: SWSE Section 36, T8S, R16E, S.L.B.&M.



SURVEYED BY: T.H.	DATE SURVEYED: 06-19-09
DRAWN BY: M.W.	DATE DRAWN: 06-25-09
SCALE: 1" = 50'	REVISED:

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078
(435) 781-2501





NEWFIELD PRODUCTION COMPANY

CROSS SECTIONS

MONUMENT BUTTE EAST R-36-8-16 (Proposed Well)

MONUMENT BUTTE EAST 15-36-8-16 (Existing Well)

Pad Location: SWSE Section 36, T8S, R16E, S.L.B.&M.



NOTE:
UNLESS OTHERWISE NOTED
CUT SLOPES ARE AT 1:1
FILL SLOPES ARE AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)				
ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	50	20	Topsoil is not included in Pad Cut	30
PIT	640	0		640
TOTALS	690	20	130	670

SURVEYED BY: T.H.	DATE SURVEYED: 06-19-09
DRAWN BY: M.W.	DATE DRAWN: 06-25-09
SCALE: 1" = 50'	REVISED:

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

Newfield Production Company Proposed Site Facility Diagram


Monument Butte East State R-36-8-16

From the Monument Butte State 15-36-8-16 Location



SW/SE Sec. 36 T8S, R16E

Duchesne County, Utah

ML-22061



Map Prepared:
Map Produced by Diana Mason



From: Jim Davis
To: Bonner, Ed; Mason, Diana
Date: 8/31/2009 9:01 AM
Subject: SITLA well approvals (Newfield 16)

CC: Garrison, LaVonne

The following wells have been approved by SITLA including arch and paleo clearance.

Monument Butte East State A-36-8-16 [API #4301350105],

Monument Butte East State J-36-8-16 [API #4301350106],

Monument Butte East State B-36-8-16 [API #4301350107],

Monument Butte East State C-36-8-16 [API #4301350108],

Monument Butte East State G-36-8-16 [API #4301350109],

Monument Butte East State M-36-8-16 [API #4301350110],

Monument Butte East State H-36-8-16 [API #4301350111],

Monument Butte State Q-36-8-16 [API #4301350113],

Monument Butte East State R-36-8-16 [API #4301350114],

Monument Butte State G-2-9-16 [API #4301350115],

South Monument Butte State M-2-9-16 [API #4301350116],

South Monument Butte State N-2-9-16 [API #4301350117],

South Monument Butte State P-2-9-16 [API #4301350118],

South Monument Butte State X-2-9-16 [API #4301350119],

South Monument Butte State V-2-9-16 [API #4301350120],

South Monument Butte State W-2-9-16 [API #4301350121]

These wells are still waiting for approvals of one kind or another:

Monument Butte East Federal V-35-8-16, Host well 2-2-9-16, no new disturbance (State surface, Federal mineral)
Monument Butte East Federal W-35-8-16, Host well 2-2-9-16, no new disturbance (State surface, Federal mineral)
Monument Butte East State K-36-8-16 [API #4301350112], Host well 9-36-8-16, new disturbance

-Jim

Jim Davis
Utah Trust Lands Administration
jimdavis1@utah.gov
Phone: (801) 538-5156

Well Name	NEWFIELD PRODUCTION COMPANY Monument Butte East State R-36-8-			
String	Surf	Prod		
Casing Size(in)	8.625	5.500		
Setting Depth (TVD)	400	6308		
Previous Shoe Setting Depth (TVD)	0	400		
Max Mud Weight (ppg)	8.3	8.6		
BOPE Proposed (psi)	0	2000		
Casing Internal Yield (psi)	2950	4810		
Operators Max Anticipated Pressure (psi)	2712	8.3		

Calculations	Surf String	8.625	"
Max BHP (psi)	$.052 \times \text{Setting Depth} \times \text{MW} =$	173	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	$\text{Max BHP} - (0.12 \times \text{Setting Depth}) =$	125	NO
MASP (Gas/Mud) (psi)	$\text{Max BHP} - (0.22 \times \text{Setting Depth}) =$	85	NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	$\text{Max BHP} - .22 \times (\text{Setting Depth} - \text{Previous Shoe Depth}) =$	85	NO OK
Required Casing/BOPE Test Pressure=		400	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient


Calculations	Prod String	5.500	"
Max BHP (psi)	$.052 \times \text{Setting Depth} \times \text{MW} =$	2821	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	$\text{Max BHP} - (0.12 \times \text{Setting Depth}) =$	2064	NO
MASP (Gas/Mud) (psi)	$\text{Max BHP} - (0.22 \times \text{Setting Depth}) =$	1433	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	$\text{Max BHP} - .22 \times (\text{Setting Depth} - \text{Previous Shoe Depth}) =$	1521	NO Reasonable for area
Required Casing/BOPE Test Pressure=		2000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		400	psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	$.052 \times \text{Setting Depth} \times \text{MW} =$		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	$\text{Max BHP} - (0.12 \times \text{Setting Depth}) =$		NO
MASP (Gas/Mud) (psi)	$\text{Max BHP} - (0.22 \times \text{Setting Depth}) =$		NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	$\text{Max BHP} - .22 \times (\text{Setting Depth} - \text{Previous Shoe Depth}) =$		NO
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	$.052 \times \text{Setting Depth} \times \text{MW} =$		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	$\text{Max BHP} - (0.12 \times \text{Setting Depth}) =$		NO
MASP (Gas/Mud) (psi)	$\text{Max BHP} - (0.22 \times \text{Setting Depth}) =$		NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	$\text{Max BHP} - .22 \times (\text{Setting Depth} - \text{Previous Shoe Depth}) =$		NO
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

43013501140000 Monument Butte East State R-36-8-16

Casing Schematic



Well name:	43013501140000 Monument Butte East State R-36-8-16		
Operator:	NEWFIELD PRODUCTION COMPANY		
String type:	Surface	Project ID:	43-013-50114
Location:	DUCHESNE COUNTY		

Design parameters:

Collapse

Mud weight: 8.330 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 80 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 108 ft

Burst

Max anticipated surface pressure: 352 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 400 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 350 ft

Non-directional string.

Re subsequent strings:

Next setting depth: 6,308 ft
Next mud weight: 8.600 ppg
Next setting BHP: 2,818 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 400 ft
Injection pressure: 400 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	400	8.625	24.00	J-55	ST&C	400	400	7.972	2059

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	173	1370	7.917	400	2950	7.38	9.6	244	25.42 J

Prepared by: Helen Sadik-Macdonald
Div of Oil,Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: September 1,2009
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 400 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43013501140000 Monument Butte East State R-36-8-16		
Operator:	NEWFIELD PRODUCTION COMPANY		
String type:	Production	Project ID:	43-013-50114
Location:	DUCHESNE COUNTY		

Design parameters:

Collapse

Mud weight: 8.600 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 162 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 1,454 ft

Burst

Max anticipated surface pressure: 1,419 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 2,797 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 5,486 ft

Directional Info - Build & Hold

Kick-off point 600 ft
Departure at shoe: 728 ft
Maximum dogleg: 1.5 °/100ft
Inclination at shoe: 7.67 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	6308	5.5	15.50	J-55	LT&C	6260	6308	4.825	22274

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	2797	4040	1.445	2797	4810	1.72	97	217	2.24 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: September 1, 2009
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 6260 ft, a mud weight of 8.6 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.



November 23, 2009

State of Utah, Division of Oil, Gas and Mining
ATTN: Diana Mason
P.O. Box 145801
Salt Lake City, UT 84114-5801

RE: Directional Drilling
Monument Butte East State R-36-8-16
Greater Monument Butte (Green River) Unit
ML-22061
Surface Hole: T8S-R16E Section 36: SWSE
842' FSL 2124' FEL

At Target: T8S-R16E Section 36: SESW
1317' FSL 2612' FWL

Duchesne County, Utah

Dear Ms. Mason;

Pursuant to the filing by Newfield Production Company (NPC) of an Application for Permit to Drill the above referenced well dated 8/17/09, a copy of which is attached, and in accordance with Oil and Gas Conservation Rule R649-3-11, NPC hereby submits this letter as notice of our intention to directionally drill this well.

The surface hole and target locations of this well are both within the boundaries of the Greater Monument Butte Unit (UTU-87538X), of which Newfield certifies that it is the operator. Further, Newfield certifies that all lands within 460 feet of the entire directional well bore are within the Greater Monument Butte Unit.

NPC is permitting this well as a directional well in order to mitigate surface disturbance by utilizing pre-existing roads and pipelines.

NPC hereby requests our application for permit to drill be granted pursuant to R649-3-11. If you have any questions or require further information, please contact the undersigned at 303-383-4197 or by email at sgillespie@newfield.com. Your consideration in this matter is greatly appreciated.

Sincerely,
Newfield Production Company

A handwritten signature in blue ink, appearing to read "Shane Gillespie".

Shane Gillespie
Land Associate

RECEIVED

NOV 30 2009

DIV. OF OIL, GAS & MINING

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

December 11, 2009

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2009 Plan of Development Greater Monument
Butte Unit, Duchesne and Uintah Counties,
Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2009 within the Greater Monument Butte Unit, Duchesne and Uintah Counties, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ GREEN RIVER)		
43-013-50112	MB East State	K-36-8-16 Sec 36 T08S R16E 2004 FSL 0706 FEL BHL Sec 36 T08S R16E 2560 FNL 0040 FEL
43-013-50111	MB East State	H-36-8-16 Sec 36 T08S R16E 1896 FNL 1955 FEL BHL Sec 36 T08S R16E 1280 FNL 2597 FEL
43-013-50110	MB East State	M-36-8-16 Sec 36 T08S R16E 1956 FNL 2075 FWL BHL Sec 36 T08S R16E 2560 FNL 2536 FWL
43-013-50109	MB East State	G-36-8-16 Sec 36 T08S R16E 1972 FNL 2061 FWL BHL Sec 36 T08S R16E 1242 FNL 1280 FWL
43-013-50108	MB East State	C-36-8-16 Sec 36 T08S R16E 0624 FNL 1996 FEL BHL Sec 36 T08S R16E 0040 FNL 2635 FEL
43-013-50107	MB East State	B-36-8-16 Sec 36 T08S R16E 0603 FNL 1995 FEL BHL Sec 36 T08S R16E 0040 FNL 1280 FEL
43-013-50106	MB East State	J-36-8-16 Sec 36 T08S R16E 0839 FNL 0604 FEL BHL Sec 36 T08S R16E 1317 FNL 0040 FEL
43-013-50105	MB East State	A-36-8-16 Sec 36 T08S R16E 0822 FNL 0591 FEL BHL Sec 36 T08S R16E 0040 FNL 0040 FEL

Page 2

API #	WELL NAME	LOCATION
(Proposed PZ GREEN RIVER)		
43-013-50114	MB East State	R-36-8-16 Sec 36 T08S R16E 0842 FSL 2124 FEL BHL Sec 36 T08S R16E 1317 FSL 2612 FWL
43-013-50149	Federal	14-29-8-16 Sec 29 T08S R16E 0679 FSL 2241 FWL
43-047-50490	Federal	6-31-8-19 Sec 31 T08S R19E 0473 FNL 1813 FWL
43-013-50061	Federal	3-27-8-16 Sec 27 T08S R16E 0748 FNL 2211 FWL
43-047-40594	Federal	10-20-8-18 Sec 20 T08S R18E 2138 FSL 3060 FWL

Our records indicate the Federal 10-20-8-18 is closer than 460 feet from the Greater Monument Butte Unit boundary.

We have no objections to permitting the wells so long as the unit operator receives an exception to the locating and siting requirements of the State of Utah (R649-3-2).

/s/ Michael L. Coulthard

bcc: File - Greater Monument Butte Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:12-11-09

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator	NEWFIELD PRODUCTION COMPANY			
Well Name	Monument Butte East State R-36-8-16			
API Number	43013501140000	APD No	1907	Field/Unit MONUMENT BUTTE
Location: 1/4,1/4	SWSE	Sec 36	Tw 8.0S	Rng 16.0E 842 FSL 2124 FEL
GPS Coord (UTM)	579714 4435674	Surface Owner		

Participants

Floyd Bartlett (DOGM), Tim Eaton (Newfield).

Regional/Local Setting & Topography

The proposed Monument Butte East State R-36-8-16 proposed oil well is to be directionally drilled from the existing pad of the Monument Butte East State 15-36-8-16 water flood injection well. No changes are planned to the existing pad. The reserve pit will be re-dug near the original location in the southeast side of the pad. The wells are on 20-acre spacing.

A field review of the site and the existing pad showed no concerns and should be suitable for drilling and operating the proposed additional wells.

SITLA owns both the surface and the minerals.

Surface Use Plan

Current Surface Use

Existing Well Pad
Wildlfe Habitat

New Road Miles	Well Pad	Src Const Material	Surface Formation
0	Width Length		

Ancillary Facilities

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetlands

Flora / Fauna

Existing Well Pad

Soil Type and Characteristics

Erosion Issues

Sedimentation Issues

Site Stability Issues

Drainage Diverson Required?

Berm Required?

Erosion Sedimentation Control Required?

Paleo Survey Run?

Paleo Potential Observed?

Cultural Survey Run?

Cultural Resources?

Reserve Pit

Site-Specific Factors

Site Ranking

Distance to Groundwater (feet) 100 to 200 5

Distance to Surface Water (feet) >1000 0

Dist. Nearest Municipal Well (ft) >5280 0

Distance to Other Wells (feet) 20

Native Soil Type Mod permeability 10

Fluid Type Fresh Water 5

Drill Cuttings Normal Rock 0

Annual Precipitation (inches) 0

Affected Populations

Presence Nearby Utility Conduits Not Present 0

Final Score 40 1 Sensitivity Level

Characteristics / Requirements

A reserve pit will be re-dug near the original location. Its dimensions are 80' x 40' x 8' deep. A 10-foot wide bench is provided around the outside. A 16-mil liner with an appropriate sub-liner is required.

Closed Loop Mud Required? N

Liner Required?

Liner Thickness 16

Pit Underlayment Required? Y

Other Observations / Comments

Floyd Bartlett
Evaluator

8/24/2009
Date / Time

Application for Permit to Drill Statement of Basis

12/14/2009

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
1907	43013501140000	LOCKED	OW	S	No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD		
Well Name	Monument Butte East State R-36-8-16		Unit	GMBU (GRRV)	
Field	MONUMENT BUTTE		Type of Work	DRILL	
Location	SWSE 36 8S 16E S 842 FSL 2124 FEL GPS Coord (UTM) 579715E 4435674N				

Geologic Statement of Basis

Newfield proposes to set 300' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 400'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 36. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Surface casing should be extended to cover the base of the moderately saline ground water.

Brad Hill
APD Evaluator

9/1/2009
Date / Time

Surface Statement of Basis

The proposed Monument Butte East State R-36-8-16 proposed oil well is to be directionally drilled from the existing pad of the Monument Butte East State 15-36-8-16 water flood injection well. No changes are planned to the existing pad. The reserve pit will be re-dug near the original location in the southeast side of the pad. The wells are on 20-acre spacing.

A field review of the site and the existing pad showed no concerns and should be suitable for drilling and operating the proposed additional wells.

SITLA owns both the surface and the minerals. They were invited to the pre-site visit but did not attend.

The Utah Division of Wildlife Resources was also invited and did not attend. Pat Rainbolt of the DWR stated on the telephone that a historic ferruginous hawk nest was in the immediate area. By e-mail he requested a timing restriction from March 1-July 15. On the pre-site visit Mr. Eaton stated he would contact UDWR and request more information about the nest and it's monitoring history. DWR would be requested to provide current year information regarding its use. By phone on 08/26/2009, Jim Davis of SITLA was informed of DWR's request. He stated he would discuss the request with Mr. Eaton of Newfield.

Floyd Bartlett
Onsite Evaluator

8/24/2009
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

WORKSHEET

APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 8/17/2009

API NO. ASSIGNED: 43013501140000

WELL NAME: Monument Butte East State R-36-8-16

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 646-4825

CONTACT: Mandie Crozier

PROPOSED LOCATION: SWSE 36 080S 160E

Permit Tech Review: ☒

SURFACE: 0842 FSL 2124 FEL

Engineering Review: ☒

BOTTOM: 1317 FSL 2612 FWL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.06945

LONGITUDE: -110.06521

UTM SURF EASTINGS: 579715.00

NORTHINGS: 4435674.00

FIELD NAME: MONUMENT BUTTE

LEASE TYPE: 3 - State

LEASE NUMBER: ML-22061

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 3 - State

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- ☒ **PLAT**
- ☒ **Bond:** STATE/FEE - B001834
- ☐ **Potash**
- ☐ **Oil Shale 190-5**
- ☐ **Oil Shale 190-3**
- ☐ **Oil Shale 190-13**
- ☒ **Water Permit:** 43-7478
- ☐ **RDCC Review:**
- ☐ **Fee Surface Agreement**
- ☐ **Intent to Commingle**

Commingleing Approved


LOCATION AND SITING:

- ☐ **R649-2-3.**
- Unit:** GMBU (GRRV)
- ☐ **R649-3-2. General**
- ☒ **R649-3-3. Exception**
- ☒ **Drilling Unit**
- Board Cause No:** Cause 213-11
- Effective Date:** 11/30/2009
- Siting:** 460' fr unit boundary
- ☒ **R649-3-11. Directional Drill**

Comments: Presite Completed

Stipulations:

- 1 - Exception Location - dmason
- 5 - Statement of Basis - bhll
- 15 - Directional - dmason
- 25 - Surface Casing - hmadonald
- 27 - Other - bhll



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Monument Butte East State R-36-8-16
API Well Number: 43013501140000
Lease Number: ML-22061
Surface Owner: STATE
Approval Date: 12/14/2009

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 213-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Exception Location:

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Surface casing shall be cemented to the surface.

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan – contact Dustin Doucet
- Significant plug back of the well – contact Dustin Doucet
- Plug and abandonment of the well – contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <https://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program – contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well – contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:



For Gil Hunt
Associate Director, Oil & Gas

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NUMBER: UTAH STATE ML-22061
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: GMBU
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: GMBU
4. LOCATION OF WELL: FOOTAGES AT SURFACE: OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: , 36, T8S, R16E		8. WELL NAME and NUMBER: <u>R-36-8-16</u> MONUMENT BUTTE EAST STATE
PHONE NUMBER 435.646.3721		9. API NUMBER: 4301350114
		10. FIELD AND POOL, OR WILDCAT: GREATER MB UNIT
		COUNTY: DUCHESNE
		STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/STOP) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARITLY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLAIR <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: - Weekly Status Report
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: <u>05/25/2010</u>			


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The above subject well was completed on 05-25-10, attached is a daily completion status report.

NAME (PLEASE PRINT) Lucy Chavez-Naupoto

TITLE Administrative Assistant

SIGNATURE



DATE 06/01/2010

(This space for State use only)

RECEIVED

JUN 07 2010

DIV. OF OIL, GAS & MINING

Daily Activity Report

Format For Sundry

MON BUTTE EAST R-36-8-16

3/1/2010 To 7/30/2010

5/14/2010 Day: 1

Completion

Rigless on 5/14/2010 - Run CBL and perforate 1st stage. - Install 5m frac head. NU 6" 5K Cameron BOP. RU hot oil truck & pressure test casing, blind rams, frac head, & casing valves to 4500 psi w/ 2 bw. RU The Perforators LLC WLT w/ mast & run CBL under pressure. WLTD @ 6235' w/ cement top @ 56'. Perforate stage #1, CP 5 sds (6060'-70') w/ 3 1/8" Port plug guns (11 gram .36" EH 16.82" pen) w/ 3 spf for a total of 30 shots. RD The Peforators LLC WLT.

Daily Cost: \$0

Cumulative Cost: \$9,301

5/18/2010 Day: 2

Completion

Rigless on 5/18/2010 - Perforate, frac & flowback 6 stages. - Perforate & frac 6 stages as detailed. 2929 BWTR. Open for immediate flowback at approx 3 BPM. Flowed for 8 1/3 hours & turned to oil & gas. Recovered 1224 bbls. 1705 BWTR.

Daily Cost: \$0

Cumulative Cost: \$131,992

5/21/2010 Day: 3

Completion

WWS #5 on 5/21/2010 - Set kill plug. MIRUSU, PU tbq. - RU WLT & hot oil truck. Check pressure on well, 800 psi. Pump 20 BW down csg. RIH w/ Weahterford 6K solid plug and set @ 4290'. RD WLT & hot oiler. Bleed pressure off well. MIRUSU. Check pressure on well, 0 psi. ND frac BOPs & frac head. NU production wellhead & BOPs. RU rig floor. Talley & PU 4 3/4" chomp bit, bit sub & 130- jts 2 7/8" J-55 6.5# 8rd EUE tbq. Circulate well clean. RU drill equipment. SWIFN. 1725 BWTR.

Daily Cost: \$0

Cumulative Cost: \$175,800

5/24/2010 Day: 4

Completion

WWS #5 on 5/24/2010 - Drill out plugs & clean out to PBTD - PU 6- jts tbq & tag plug @ 4290'. Drill out plug in 29 min. Continue PU tbq & tag plug @ 4510'. Drill out plug in 40 min. Continue PU tbq & tag plug @ 5100'. Drill out plug in 28 min. Transfer 80 BW up flowline. Continue PU tbq & tag plug @ 5280'. Drill out plug in 26 min. Continue PU tbq & tag plug @ 5540'. Drill out plug in 23 min. Continue PU tbq & tag plug @ 5998'. Drill out plug in 41 min. Continue PU tbq & tag fill @ 6084'. Clean out to PBTD @ 6199'. Circulate well clean. RD drill equipment. LD 3 jts tbq & place EOT @ 6127'. Left well flowing up flowline for weekend w/ 24/64" choke. SDFN. 1345 BWTR.

Daily Cost: \$0

Cumulative Cost: \$186,563

5/25/2010 Day: 5

Completion

WWS #5 on 5/25/2010 - Round trip tbq & PU rods. - Check pressure on well, 450 psi csg & 80 psi tbq. Pump 30 bbls brine down tbq. PU 3- jts tbq. Tag PBTD @ 6199'. Circulate well clean

w/ 250 bbls brine. LD 3- jts tbg & TOOH w/ tbg. TIH w/ production tbg as detailed. RD rig floor. ND BOPs. Set TA @ 6038' w/ 18,000#s tension. NU wellhead. X-over for rods. Pump 60 bbls brine down tbg. PU & prime Central Hydraulic 2 1/2" X 1 3/4" X 20' X 24' RHAC rod pump. PU rod string as detailed. RU pumping unit. Stroke test pump w/ unit to 800 psi. RDMOSU. PWOP @ 6:30 pm w/ 144" SL & 5 SPM. 1001 BWTR. **Finalized**

Daily Cost: \$0

Cumulative Cost: \$228,201

Pertinent Files: Go to File List

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well ☒ Oil Well ☐ Gas Well ☐ Dry ☐ Other
b. Type of Completion: ☒ New Well ☐ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resvr.,
Other: _____

2. Name of Operator
NEWFIELD EXPLORATION COMPANY

3. Address
1401 17TH ST. SUITE 1000 DENVER, CO 80202

3a. Phone No. (include area code)
(435)646-3721

4. Location of Well (Report location clearly and in accordance with Federal requirements)*

At surface 842' FSL & 2124' FEL (SW/SE) SEC. 36, T8S, R16E (ML-22061)

At top prod. interval reported below 1199' FSL & 2553' FEL (SW/SE) SEC. 36, T8S, R16E (ML-22061)

At total depth 1409' FSL 2478' FWL (NE/SW) SEC. 36, T8S, R16E (ML-22061)

14. Date Spudded
04/22/2010

15. Date T.D. Reached
05/04/2010

16. Date Completed 05/24/2010
☐ D & A ☒ Ready to Prod.

9. AFI Well No.
43-013-50114

10. Field and Pool or Exploratory
MONUMENT BUTTE

11. Sec., T., R., M., on Block and
Survey or Area
SEC. 36, T8S, R16E

12. County or Parish
DUCHESENE

13. State
UT

17. Elevations (DF, RKB, RT, GL)*
5355' GL 5367' KB

18. Total Depth: MD 6255'
TVD 6181'

19. Plug Back T.D.: MD 6199'
TVD 6125'

20. Depth Bridge Plug Set: MD
TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)

DUAL IND GRD, SP, COMP. DENSITY, COMP. NEUTRON, GR, CALIPER, CMT BOND

22. Was well cored? ☒ No ☐ Yes (Submit analysis)
Was DST run? ☒ No ☐ Yes (Submit report)
Directional Survey? ☐ No ☒ Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12-1/4"	8-5/8" J-55	24#	0	442'		200 CLASS G			
7-7/8"	5-1/2" J-55	15.5#	0	6245'		228 PRIMLITE		64'	
						401 50/50 POZ			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2-7/8"	EOT @ 6106'	TA @ 6038'						

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) Green River			6060-6070' CP5	.36"	3	30
B) Green River			5923-5933' CP4	.36"	3	30
C) Green River			5420-5455' A3	.36"	3	24
D) Green River			5158-5210' B1 B2	.36"	3	42

27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Depth Interval	Amount and Type of Material
6060-6070'	Frac w/ 55316#s 20/40 sand in 352 bbls of Lightning 17 fluid.
5923-5933'	Frac w/ 35030#s 20/40 sand in 176 bbls of Lightning 17 fluid.
5420-5455'	Frac w/ 40341#s 20/40 sand in 266 bbls of Lightning 17 fluid.
5158-5210'	Frac w/ 75800#s 20/40 sand in 453 bbls of Lightning 17 fluid.

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
5-24-10	6-9-10	24	→	33	0	6.26			2-1/2" x 1-3/4" x 20' x 24' RHAC Pump
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→					PRODUCING	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

*(See instructions and spaces for additional data on page 2)

RECEIVED

JUN 21 2010

DIV. OF OIL, GAS & MINING

28b. Production - Interval C									
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

28c. Production - Interval D									
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

USED FOR FUEL

30. Summary of Porous Zones (Include Aquifers):	31. Formation (Log) Markers
Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.	GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GARDEN GULCH MRK GARDEN GULCH 1	3836' 4041'
				GARDEN GULCH 2 POINT 3	4160' 4434'
				X MRKR Y MRKR	4682' 4717'
				DOUGALS CREEK MRK BI CARBONATE MRK	4843' 5090'
				B LIMESTON MRK CASTLE PEAK	5223' 5706'
				BASAL CARBONATE	6143'

32. Additional remarks (include plugging procedure):

Stage 5: Green River Formation (D1 D2 & C) 4878-5034', .36" 3/21 Frac w/ 40512#'s of 20/40 sand in 255 bbls of Lightning 17 fluid

Stage 5: Green River Formation (GB4 & GB6) 4340-4429', .36" 3/18 Frac w/ 50163#'s of 20/40 sand in 314 bbls of Lightning 17 fluid

33. Indicate which items have been attached by placing a check in the appropriate boxes:


- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: Drilling Daily Activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Lucy Chavez-Naupoto

Title Administrative Assistant

Signature



Date 06/17/2010

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)

NEWFIELD



NEWFIELD EXPLORATION

**USGS Myton SW (UT)
SECTION 36 T8S, R16E
R-36-8-16**

Wellbore #1

Design: Actual

Standard Survey Report

07 June, 2010

HATHAWAY ^{HB} BURNHAM
DIRECTIONAL & MWD SERVICES



HATHAWAY BURNHAM

Survey Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 36 T8S, R16E
Well: R-36-8-16
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well R-36-8-16
TVD Reference: R-36-8-16 @ 5367.0ft
MD Reference: R-36-8-16 @ 5367.0ft
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Project	USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		

Site	SECTION 36 T8S, R16E, SEC 26 T8S, R16E		
Site Position:		Northing:	7,202,697.00 ft
From:	Lat/Long	Easting:	2,045,250.00 ft
Position Uncertainty:	0.0 ft	Slot Radius:	"
		Latitude:	40° 5' 3.401 N
		Longitude:	110° 3' 10.915 W
		Grid Convergence:	0.93 °

Well	R-36-8-16, SHL LAT: 40 04 09.95, LONG: -110 03 57.34		
Well Position	+N/-S	0.0 ft	Northing: 7,197,231.22 ft
	+E/-W	0.0 ft	Easting: 2,041,728.99 ft
Position Uncertainty	0.0 ft	Wellhead Elevation:	ft
		Latitude:	40° 4' 9.950 N
		Longitude:	110° 3' 57.340 W
		Ground Level:	5,337.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	2009/07/16	11.55	65.87	52,503

Design	Actual				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.0	0.0	0.0	310.04	

Survey Program	Date 2010/06/07				
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
475.0	6,255.0	Survey #1 (Wellbore #1)	MWD	MWD - Standard	

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
475.0	0.55	224.63	475.0	-1.6	-1.6	0.2	0.12	0.12	0.00
506.0	0.68	231.36	506.0	-1.8	-1.8	0.2	0.48	0.42	21.71
536.0	0.73	233.65	536.0	-2.1	-2.1	0.3	0.19	0.17	7.63
567.0	0.66	243.12	567.0	-2.3	-2.5	0.4	0.43	-0.23	30.55
597.0	0.77	259.79	597.0	-2.4	-2.8	0.6	0.78	0.37	55.57
628.0	0.79	270.56	628.0	-2.4	-3.2	0.9	0.48	0.06	34.74
659.0	0.90	286.58	659.0	-2.3	-3.7	1.3	0.84	0.35	51.68
690.0	1.03	295.06	690.0	-2.2	-4.2	1.8	0.62	0.42	27.35
720.0	1.32	303.43	720.0	-1.9	-4.7	2.4	1.12	0.97	27.90
751.0	1.71	310.09	751.0	-1.4	-5.3	3.2	1.38	1.26	21.48
781.0	1.96	313.12	780.9	-0.7	-6.1	4.2	0.89	0.83	10.10
812.0	2.48	320.22	811.9	0.2	-6.9	5.4	1.89	1.68	22.90



HATHAWAY BURNHAM

Survey Report



Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 36 T8S, R16E
 Well: R-36-8-16
 Wellbore: Wellbore #1
 Design: Actual

Local Co-ordinate Reference: Well R-36-8-16
 TVD Reference: R-36-8-16 @ 5367.0ft
 MD Reference: R-36-8-16 @ 5367.0ft
 North Reference: True
 Survey Calculation Method: Minimum Curvature
 Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
857.0	3.14	315.72	856.9	1.8	-8.4	7.6	1.55	1.47	-10.00
903.0	3.60	322.80	902.8	3.8	-10.1	10.2	1.35	1.00	15.39
948.0	4.02	317.01	947.7	6.1	-12.0	13.2	1.26	0.93	-12.87
993.0	4.60	321.60	992.6	8.7	-14.2	16.5	1.50	1.29	10.20
1,039.0	5.30	320.09	1,038.4	11.8	-16.8	20.4	1.55	1.52	-3.28
1,084.0	5.70	318.40	1,083.2	15.0	-19.6	24.7	0.96	0.89	-3.76
1,129.0	6.53	315.23	1,127.9	18.5	-22.9	29.4	1.99	1.84	-7.04
1,174.0	7.21	315.28	1,172.6	22.3	-26.6	34.8	1.51	1.51	0.11
1,220.0	7.70	316.20	1,218.2	26.6	-30.8	40.7	1.10	1.07	2.00
1,265.0	8.31	313.60	1,262.8	31.0	-35.3	47.0	1.58	1.36	-5.78
1,310.0	8.81	315.58	1,307.3	35.7	-40.0	53.6	1.29	1.11	4.40
1,356.0	9.40	312.88	1,352.7	40.8	-45.2	60.9	1.58	1.28	-5.87
1,401.0	10.13	313.89	1,397.0	46.1	-50.8	68.5	1.67	1.62	2.24
1,492.0	10.72	313.00	1,486.5	57.4	-62.7	84.9	0.67	0.65	-0.98
1,582.0	11.07	311.78	1,574.9	68.8	-75.3	101.9	0.47	0.39	-1.36
1,673.0	11.70	309.20	1,664.1	80.5	-89.0	119.9	0.89	0.69	-2.84
1,763.0	10.50	309.23	1,752.4	91.4	-102.4	137.2	1.33	-1.33	0.03
1,854.0	9.80	302.50	1,842.0	100.9	-115.3	153.2	1.51	-0.77	-7.40
1,945.0	8.75	301.43	1,931.8	108.6	-127.8	167.7	1.17	-1.15	-1.18
2,035.0	8.30	299.41	2,020.8	115.4	-139.3	180.9	0.60	-0.50	-2.24
2,126.0	8.61	301.61	2,110.8	122.2	-150.8	194.1	0.49	0.34	2.42
2,217.0	8.90	305.37	2,200.8	129.8	-162.4	207.8	0.70	0.32	4.13
2,307.0	9.00	308.30	2,289.7	138.2	-173.6	221.8	0.52	0.11	3.26
2,398.0	9.10	310.70	2,379.6	147.3	-184.6	236.1	0.43	0.11	2.64
2,488.0	9.90	313.50	2,468.3	157.3	-195.6	250.9	1.03	0.89	3.11
2,579.0	9.50	309.00	2,558.0	167.4	-207.1	266.3	0.94	-0.44	-4.95
2,670.0	9.10	303.80	2,647.8	176.1	-218.9	280.9	1.02	-0.44	-5.71
2,760.0	9.10	303.40	2,736.7	184.0	-230.8	295.1	0.07	0.00	-0.44
2,851.0	9.20	308.80	2,826.5	192.5	-242.5	309.5	0.95	0.11	5.93
2,941.0	10.10	314.50	2,915.3	202.6	-253.7	324.5	1.46	1.00	6.33
3,032.0	10.40	320.30	3,004.8	214.5	-264.6	340.6	1.18	0.33	6.37
3,123.0	11.10	319.60	3,094.2	227.5	-275.6	357.3	0.78	0.77	-0.77
3,213.0	10.60	312.10	3,182.6	239.6	-287.3	374.1	1.66	-0.56	-8.33
3,304.0	9.80	307.40	3,272.2	249.9	-299.7	390.2	1.27	-0.88	-5.16
3,394.0	10.80	308.80	3,360.7	259.9	-312.3	406.3	1.15	1.11	1.56
3,485.0	10.92	305.76	3,450.1	270.2	-326.0	423.4	0.64	0.13	-3.34
3,576.0	10.80	304.60	3,539.5	280.1	-340.0	440.5	0.27	-0.13	-1.27
3,666.0	10.80	305.10	3,627.9	289.8	-353.8	457.3	0.10	0.00	0.56
3,757.0	9.90	303.10	3,717.4	298.9	-367.4	473.6	1.06	-0.99	-2.20
3,847.0	8.90	305.10	3,806.2	307.2	-379.5	488.2	1.17	-1.11	2.22
3,938.0	8.00	309.50	3,896.2	315.2	-390.2	501.5	1.22	-0.99	4.84
4,028.0	8.42	316.00	3,985.3	324.0	-399.6	514.3	1.13	0.47	7.22
4,119.0	9.27	319.82	4,075.2	334.4	-408.9	528.2	1.13	0.93	4.20
4,210.0	9.65	318.37	4,165.0	345.7	-418.7	543.0	0.49	0.42	-1.59
4,300.0	9.65	316.57	4,253.7	356.8	-428.9	557.9	0.34	0.00	-2.00
4,391.0	10.15	311.25	4,343.3	367.6	-440.2	573.5	1.14	0.55	-5.85
4,481.0	10.68	309.08	4,431.8	378.1	-452.6	589.8	0.73	0.59	-2.41
4,572.0	9.60	306.00	4,521.4	387.9	-465.3	605.8	1.33	-1.19	-3.38
4,663.0	9.51	307.90	4,611.2	396.9	-477.4	620.9	0.36	-0.10	2.09
4,753.0	9.65	312.38	4,699.9	406.6	-488.8	635.8	0.84	0.16	4.98
4,844.0	9.10	311.67	4,789.7	416.5	-499.9	650.6	0.62	-0.60	-0.78
4,934.0	9.34	311.00	4,878.5	426.0	-510.7	665.1	0.29	0.27	-0.74
5,025.0	9.10	307.50	4,968.3	435.3	-522.0	679.6	0.67	-0.26	-3.85
5,116.0	8.40	308.00	5,058.3	443.7	-532.9	693.5	0.77	-0.77	0.55



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 36 T8S, R16E
Well: R-36-8-16
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well R-36-8-16
TVD Reference: R-36-8-16 @ 5367.0ft
MD Reference: R-36-8-16 @ 5367.0ft
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,206.0	8.60	312.60	5,147.3	452.3	-543.0	706.8	0.79	0.22	5.11
5,297.0	8.70	321.60	5,237.3	462.3	-552.3	720.3	1.49	0.11	9.89
5,387.0	8.70	318.60	5,326.2	472.8	-561.1	733.7	0.50	0.00	-3.33
5,478.0	8.90	320.70	5,416.2	483.4	-570.1	747.4	0.42	0.22	2.31
5,569.0	9.60	314.50	5,506.0	494.2	-579.9	761.9	1.34	0.77	-6.81
5,659.0	9.20	306.50	5,594.8	503.7	-591.1	776.6	1.52	-0.44	-8.89
5,750.0	9.30	304.60	5,684.6	512.2	-603.0	791.1	0.35	0.11	-2.09
5,840.0	10.26	303.72	5,773.3	520.8	-615.6	806.4	1.08	1.07	-0.98
5,931.0	10.88	306.62	5,862.7	530.4	-629.3	823.0	0.90	0.68	3.19
6,255.0	10.88	306.62	6,180.9	566.9	-678.3	884.0	0.00	0.00	0.00

R-36-8-16 TGT


Wellbore Targets

Target Name

- hit/miss target	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
- Shape									
R-36-8-16 TGT	0.00	0.00	6,260.0	468.0	-556.9	7,197,690.23	2,041,164.62	40° 4' 14.575 N	110° 4' 4.505 W
- actual wellpath misses by 175.4ft at 6255.0ft MD (6180.9 TVD, 566.9 N, -678.3 E)									
- Circle (radius 75.0)									

Checked By: _____ Approved By: _____ Date: _____

NEWFIELD





Project: USGS Myton SW (UT)
 Site: SECTION 36 T8S, R16E
 Well: R-36-8-16
 Wellbore: Wellbore #1
 SURVEY: Actual

FINAL SURVEY REPORT



Azimuths to True North
 Magnetic North: 11.55°

Magnetic Field
 Strength: 52503.4snT
 Dip Angle: 65.87°
 Date: 2009/07/16
 Model: IGRF200510



HATHAWAY HBBURNHAM
 DIRECTIONAL & MWD SERVICES

Design: Actual (R-36-8-16/Wellbore #1)

Created By: *Tim Hudson* Date: 20:51, June 07 2010
 THIS SURVEY IS CORRECT TO THE BEST OF MY
 KNOWLEDGE AND IS SUPPORTED BY ACTUAL FIELD DATA.

Daily Activity Report

Format For Sundry

MON BUTTE EAST R-36-8-16**2/1/2010 To 6/30/2010****MON BUTTE EAST R-36-8-16****Waiting on Cement****Date:** 4/23/2010

Ross #21 at 440. Days Since Spud - On 4/25/10 Cemented 8 5/8" Casing W/ BJ Services, Pumped 200sks Class "G"+2%CaCl - I+.25#sk Cello Flake Mixed@ 15.8ppg W/1.17 yield, returned 4bbbs to pit. - Spud on 4/22/10 W/ Ross Rig # 21 @ 9:00 AM. Drilled 440' of 12 1/4" hole. Run 8 jts 8 5/8" - Csg. (Guide shoe, Shoe Jt. Baffle Plate 9jts) Set @ 441.82'KB

Daily Cost: \$0**Cumulative Cost:** \$55,794**MON BUTTE EAST R-36-8-16****Rigging down****Date:** 5/1/2010

Capstar #328 at 440. 0 Days Since Spud - Rigging down Getting ready to move the rig to the Monumont Butte East State R-36-8-16 on 5/1/10

Daily Cost: \$0**Cumulative Cost:** \$56,144**MON BUTTE EAST R-36-8-16****Drill 7 7/8" hole with fresh water****Date:** 5/2/2010

Capstar #328 at 2266. 1 Days Since Spud - PU BHA Smith MI 616 PDC, Dog sub, Hunting MM 7/8 mil, 4.8 stage, .33, NMDC, Gap sub, Ant sub, - min tests ok Accept rig @ 2:00 PM on 5/1/10 - Blind rams & Floor valve to 2000#s for 10 min & Casing to 1500#s for 30 min & Hydril to 1500#s f/ 10 - Hold saftey mtg w/ B&C Quick test & Test Upper kelly valve Pipe rams inside & outside choke valves & - Drill 77/8" hole f/ 386 to 2266' WOB 15/18, GPM= 409 RPMS= 184 ROP= 163 pr hr - NMDC, 4.5 HWDP - TIH & Tag cmt @ 386' - Nipple Bops - RU - On 5/1/10 Moved rig w/ Howcroft Trucking 1 mile to the Monumont Butte East State R-36-8-16

Daily Cost: \$0**Cumulative Cost:** \$101,614**MON BUTTE EAST R-36-8-16****Drill 7 7/8" hole with fresh water****Date:** 5/3/2010

Capstar #328 at 5030. 2 Days Since Spud - Drill 77/8" hole f/ 2266' to 3490' WOB 20/25, GPM= 409 RPMS= 184 ROP= 174' pr hr - Rig serv - Drill 77/8" hole f/ 3490' to 5030' WOB 20/25, GPM= 409 RPMS= 184 ROP= 93' pr hr - No H2S in the last 24 hrs

Daily Cost: \$0**Cumulative Cost:** \$121,363**MON BUTTE EAST R-36-8-16****Logging****Date:** 5/4/2010

Capstar #328 at 6255. 3 Days Since Spud - Rig serv - Drill 77/8 hole f/ 5664' to 5983' WOB 20/25, GPM= 409 RPMS= 184 ROP= 79' pr hr - Trouble shoot dirc tools, Did not get tools to work - We rotated out f/ 5983' to 6255' WOB 20/25, GPM= 409 RPMS= 184 ROP= 136' pr hr, No surveys - Circ f/ laydown - LDDP & BHA - RU Phoenix Survey - Drill 77/8 hole f/ 5030 to 5664' WOB 20/25, GPM= 409 RPMS= 184 ROP= 79' pr hr

Daily Cost: \$0**Cumulative Cost:** \$159,427

MON BUTTE EAST R-36-8-16**Rigging down****Date:** 5/5/2010

Capstar #328 at 6255. 4 Days Since Spud - Loggers TD 6236' - RU & run 143 jts of 5.5 casing J55 15.5# LT&C shoe @ 6245.55' Float collar 6198.72', 5 jts transferr - d to the Greate Boundary B-1-9-16 - Circ f/ cement - Hold saftey mtg & RU BJ & cement w/ 228 sks of lead cmt 11 ppg & 3.53 yeild PLII+3%KCL+5#CSE+0.5CF+ - RU Phoenix survey & Log w/ Duel Guard Gamma Ray Compensated Density Compensated Neutron Gamma Ray - SMS+FP-6L Disp 147.7 bbls Returned 15 bbls of cmt to pit Bumped plug to 2200#s - Nipple down & set 5.5 casing slips w/ 87,000#s - Clean mud pits - Release rig @ 12:00 AM on 5/5/10 - 5#KOL+.5SMS+FP+SF & 401sks of tail cmt 14.4 ppg & 1.24 yeild 50:50:2+3%KCL+0.5%EC-1+.25#CF+.05#SF+.3 **Finalized**

Daily Cost: \$0**Cumulative Cost:** \$271,720

Pertinent Files: Go to File List

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS


Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NUMBER: UTAH STATE ML-22061
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: GMBU
4. LOCATION OF WELL: FOOTAGES AT SURFACE:		8. WELL NAME and NUMBER: <u>R 30-8-16</u> MONUMENT BUTTE EAST STATE
OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: , 36, T8S, R16E		9. API NUMBER: 4301350114
COUNTY: DUCHESNE		10. FIELD AND POOL, OR WILDCAT: GREATER MB UNIT
STATE: UT		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/STOP) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARITLY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLAIR <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: - Spud Notice
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: <u>04/28/2010</u>			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 4/22/2010 MIRU Ross # 21. Spud well @ 9:00 AM. Drill 440' of 12 1/4" hole with air mist. TIH W/ 10 Jt's 8 5/8" J-55 24 # csgn. Set @ 441'/KB On 4/25/2010 cement with 200 sks of class "G" w/ 3% CaCL2 + 1/4# sk Cello- Flake Mixed @ 15.8 ppg > 1.17 cf/ sk yeild. Returned 5 bbls cement to pit. WOC.

NAME (PLEASE PRINT) <u>Justin Crum</u>	TITLE <u>Drilling Foreman</u>
SIGNATURE 	DATE <u>04/29/2010</u>

(This space for State use only)

RECEIVED

MAY 11 2010

DIV. OF OIL, GAS & MINING

NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

8 5/8" CASING SET AT 441.82

LAST CASING	<u>14</u>	SET AT	<u>4</u>
DATUM	<u>13</u>		
DATUM TO CUT OFF CASING		<u>13</u>	
DATUM TO BRADENHEAD FLANGE		<u>13</u>	
TD DRILLER	<u>440</u>	LOGGER	<u> </u>
HOLE SIZE	<u>12 1/4"</u>		

OPERATOR Newfield Exploration Company
WELL MON BUTTE EAST R-36-8-16
FIELD/PROSPECT Mon. Butte
CONTRACTOR & RIG # Ross Rig # 21

LOG OF CASING STRING:

[illegible]

[illegible]

COMPANY REPRESENTATIVE

DATE **4/25/2010**

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM -FORM 6

OPERATOR: NEWFIELD PRODUCTION COMPANY
ADDRESS: RT. 3 BOX 3630
MYTON, UT 84052

OPERATOR ACCT. NO. N2695

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION				COUNTY	SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG			
A	99999	17592	4304740499	UTE TRIBAL 7-29-4-1E	SWNE	29	4S	1E	UINTAH	4/24/2010	4/28/10
WELL 1 COMMENTS: GRPV											
B	99999	17400	4301350209	GREATER MON BUTTE B-1-9-16	SWSE	36	8S	16E	DUCHESNE	4/23/2010	4/28/10
GRPV BHL = T9S R16E Sec 1 NWNE											
A	99999	17593	4304740501	UTE TRIBAL 8-30-4-1E	SENE	30	4S	1E	UINTAH	4/15/2010	4/28/10
GRPV											
A	99999	17594	4301350206	HANCOCK 6-21-4-1	SESE	21	4S	1W	DUCHESNE	4/19/2010	4/28/10
GRPV SENW											
B	99999	17400	4301334172	FEDERAL 12-29-8-16	NWSW	29	8S	16E	DUCHESNE	4/22/2010	4/28/10
WELL 5 COMMENTS: GRPV											
B	99999	17400	4301350114	MON BUTTE EAST STATE R-36-8-16	SWSE	36	8S	16E	DUCHESNE	4/22/2010	4/28/10
WELL 5 COMMENTS: GRPV BHL = SE SW											

ACTION CODES (See instructions on back of form)


- A - 1 new entity for new well (single well only)
- B - well to existing entity (group or unit well)
- C - from one existing entity to another existing entity
- D - well from one existing entity to a new entity
- E - ther (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

RECEIVED

APR 22 2010

DIV. OF OIL, GAS & MINING

Signature: 
Jentri Park
Production Clerk
Date: 04/22/10

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS


Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER			5. LEASE DESIGNATION AND SERIAL NUMBER: UTAH STATE ML-22061
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY			6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		PHONE NUMBER 435.646.3721	7. UNIT or CA AGREEMENT NAME: GMBU
4. LOCATION OF WELL: FOOTAGES AT SURFACE:			8. WELL NAME and NUMBER: R 30-8-16 MONUMENT BUTTE EAST STATE
OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: , 36, T8S, R16E			9. API NUMBER: 4301350114
COUNTY: DUCHESNE			10. FIELD AND POOL, OR WILDCAT: GREATER MB UNIT
STATE: UT			

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/STOP) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARITLY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLAIR <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: - Spud Notice
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: <u>04/28/2010</u>			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 4/22/2010 MIRU Ross # 21. Spud well @ 9:00 AM. Drill 440' of 12 1/4" hole with air mist. TIH W/ 10 Jt's 8 5/8" J-55 24 # csgn. Set @ 441'/KB On 4/25/2010 cement with 200 sks of class "G" w/ 3% CaCL2 + 1/4# sk Cello- Flake Mixed @ 15.8 ppg > 1.17 cf/ sk yeild. Returned 5 bbls cement to pit. WOC.

NAME (PLEASE PRINT) <u>Justin Crum</u>	TITLE <u>Drilling Foreman</u>
SIGNATURE 	DATE <u>04/29/2010</u>

(This space for State use only)

RECEIVED

MAY 11 2010

DIV. OF OIL, GAS & MINING

NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

8 5/8" CASING SET AT 441.82

LAST CASING	<u>14</u>	SET AT	<u>4</u>
DATUM	<u>13</u>		
DATUM TO CUT OFF CASING		<u>13</u>	
DATUM TO BRADENHEAD FLANGE		<u>13</u>	
TD DRILLER	<u>440</u>	LOGGER	<u> </u>
HOLE SIZE	<u>12 1/4"</u>		

OPERATOR Newfield Exploration Company
WELL MON BUTTE EAST R-36-8-16
FIELD/PROSPECT Mon. Butte
CONTRACTOR & RIG # Ross Rig # 21

LOG OF CASING STRING:

[illegible]

[illegible]

COMPANY REPRESENTATIVE

DATE **4/25/2010**

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM -FORM 6

OPERATOR: NEWFIELD PRODUCTION COMPANY
ADDRESS: RT. 3 BOX 3630
MYTON, UT 84052

OPERATOR ACCT. NO. N2695

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION				COUNTY	SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG			
A	99999	17592	4304740499	UTE TRIBAL 7-29-4-1E	SWNE	29	4S	1E	UINTAH	4/24/2010	4/28/10
WELL 1 COMMENTS: GRV											
B	99999	17400	4301350209	GREATER MON BUTTE B-1-9-16	SWSE	36	8S	16E	DUCHESNE	4/23/2010	4/28/10
GRV BHL = T9S R16E Sec 1 NWNE											
A	99999	17593	4304740501	UTE TRIBAL 8-30-4-1E	SENE	30	4S	1E	UINTAH	4/15/2010	4/28/10
GRV											
A	99999	17594	4301350206	HANCOCK 6-21-4-1	SESE	21	4S	1W	DUCHESNE	4/19/2010	4/28/10
GRV SENW											
B	99999	17400	4301334172	FEDERAL 12-29-8-16	NWSW	29	8S	16E	DUCHESNE	4/22/2010	4/28/10
WELL 5 COMMENTS: GRV											
B	99999	17400	4301350114	MON BUTTE EAST STATE R-36-8-16	SWSE	36	8S	16E	DUCHESNE	4/22/2010	4/28/10
WELL 5 COMMENTS: GRV BHL = SE SW											

ACTION CODES (See instructions on back of form)


- A - 1 new entity for new well (single well only)
- B - well to existing entity (group or unit well)
- C - from one existing entity to another existing entity
- D - well from one existing entity to a new entity
- E - ther (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

RECEIVED

APR 22 2010

DIV. OF OIL, GAS & MINING

Signature: 
Jentri Park
Production Clerk
Date: 04/22/10